September 1992 NSRP 0383

SHIP PRODUCTION COMMITTEE
FACILITIES AND ENVIRONMENTAL EFFECTS
SURFACE PREPARATION AND COATINGS
DESIGN/PRODUCTION INTEGRATION
HUMAN RESOURCE INNOVATION
MARINE INDUSTRY STANDARDS
WELDING
INDUSTRIAL ENGINEERING
EDUCATION AND TRAINING

# THE NATIONAL SHIPBUILDING RESEARCH PROGRAM

1992 Ship Production Symposium Proceedings

Paper No.7A-1: An Approach to a New Ship Production System Based on Advanced Accuracy Control

U.S. DEPARTMENT OF THE NAVY CARDEROCK DIVISION, NAVAL SURFACE WARFARE CENTER

maintaining the data needed, and c including suggestions for reducing	lection of information is estimated to completing and reviewing the collect this burden, to Washington Headqu uld be aware that notwithstanding ar DMB control number.	ion of information. Send comments arters Services, Directorate for Infor	regarding this burden estimate of mation Operations and Reports	or any other aspect of th , 1215 Jefferson Davis I	is collection of information, Highway, Suite 1204, Arlington	
1. REPORT DATE SEP 1992		2. REPORT TYPE <b>N/A</b>		3. DATES COVE	RED	
4. TITLE AND SUBTITLE			5a. CONTRACT NUMBER			
	building Research P edings, Paper No. 7A	5b. GRANT NUM	IBER			
<b>Production System</b>	Based on Advanced	d Accuracy Control	-	5c. PROGRAM E	LEMENT NUMBER	
6. AUTHOR(S)				5d. PROJECT NU	MBER	
				5e. TASK NUMB	ER	
				5f. WORK UNIT NUMBER		
Naval Surface War	ZATION NAME(S) AND AD refere Center CD Coc 8 9500 MacArthur	de 2230-Design Inte	0	8. PERFORMING REPORT NUMBI	ORGANIZATION ER	
9. SPONSORING/MONITO	RING AGENCY NAME(S) A	AND ADDRESS(ES)		10. SPONSOR/M	ONITOR'S ACRONYM(S)	
				11. SPONSOR/MONUMBER(S)	ONITOR'S REPORT	
12. DISTRIBUTION/AVAIL Approved for publ	LABILITY STATEMENT ic release, distributi	on unlimited				
13. SUPPLEMENTARY NO	OTES					
14. ABSTRACT						
15. SUBJECT TERMS						
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT	18. NUMBER OF PAGES	19a. NAME OF RESPONSIBLE PERSON	
a. REPORT unclassified	ь. ABSTRACT <b>unclassified</b>	c. THIS PAGE unclassified	SAR	14	RESI CINSIBLE FERSUN	

**Report Documentation Page** 


Form Approved OMB No. 0704-0188

# DISCLAIMER

These reports were prepared as an account of government-sponsored work. Neither the United States, nor the United States Navy, nor any person acting on behalf of the United States Navy (A) makes any warranty or representation, expressed or implied, with respect to the accuracy, completeness or usefulness of the information contained in this report/manual, or that the use of any information, apparatus, method, or process disclosed in this report may not infringe privately owned rights; or (B) assumes any liabilities with respect to the use of or for damages resulting from the use of any information, apparatus, method, or process disclosed in the report. As used in the above, "Persons acting on behalf of the United States Navy" includes any employee, contractor, or subcontractor to the contractor of the United States Navy to the extent that such employee, contractor, or subcontractor to the contractor prepares, handles, or distributes, or provides access to any information pursuant to his employment or contract or subcontract to the contractor with the United States Navy. ANY POSSIBLE IMPLIED WARRANTIES OF MERCHANTABILITY AND/OR FITNESS FOR PURPOSE ARE SPECIFICALLY DISCLAIMED.


## THE NATIONAL SHIPBUILDING RESEARCH PROGRAM

# 1992 SHIP PRODUCTION SYMPOSIUM



SEPTEMBER 2 - 4, 1992 New Orleans Hyatt Regency NEW ORLEANS, LOUISIANA





SPONSORED BY THE SHIP PRODUCTION COMMITTEE
AND HOSTED BY THE GULF SECTION OF
THE SOCIETY OF NAVAL ARCHITECTS AND MARINE ENGINEERS



# THE SOCIETY OF NAVAL ARCHITECTS AND MARINE ENGINEERS 601 PAVONIA AVENUE, JERSEY CITY, NJ 07306

Paper proseuted at the NSRP 1992 slup Production Symposium. New Orleans Hyatt Regency. New Orleans. Lousuana,. September 24. 1992.

# An Approach to a New Ship Production No. 7A-1 System Based on Advanced Accuracy Control

Masaaki Yuuzaki, Visitor, and Yasuhisa Okumato, Visitor, Ishikawajima-Harima Heavy Industries Co. Ltd.

#### ABSTRACT

Mechanizing and automating have been accelerated in shipbuilding in order to respond to current situations such as decreasing numbers of skilled workers and increasing difficulty in recruiting new workers.

For effective implementation of mechanization or automation, current hull fabrication systems should be reviewed in order to make them suitable for intended mechanization or automation because geometric inaccuracy hampers implementation and necessitates voluminous work adjustments.

This report proposes a new ship production concept based on using advanced methods to keep the accuracy of the hull structure at a high level, such as numerical simulation of heat deformation in burning, welding and bending, mechanizing to reduce deviations dependent on human skill, and a three-dimensional measuring system for advanced accuracy control together with some examples of its actual application to checking block shape at the assembly stage and shipwrighting at the erection site.

#### INTRODUCTION

To maintain the competitiveness of a shipyard bearing the hardships surrounding the Japanese shipbuilding industry mentioned in the abstract, the extensive application of mechanization and automation is recognized to be indispensable at Ishikawajima-Harima Heavy Industries Co., Ltd, (IHI) and this can only be realized by upgraded accuracy. From this standpoint, to make an accurate block and to erect it accurately are the major task of current hull personnel in the shipyard.

This paper describes the recent efforts of how the company is rising to the challenge of accuracy of hull structure.

#### RECOGNITION OF THE PROBLEM

Since the latter half of 1950s when the idea of quality control was introduced in Japan, hull accuracy control concepts have been developed and widely used in each stage of hull work and with this a remarkable productivity improvement has resulted. However, looking at the final goal of having assembled blocks fitted and welded at the erection site without any remedial adjustment, it must be said that the present situation is still far from ideal.

Some recent analyses at the shipyards are explained below to demonstrate the current situation.

# Manhour Analyses on Fitting and Welding at Erection Stage

Fig. 1 shows the percentages of expended manhours of fitting and welding work in the hull erection stage based on random sampling carried out in one shipyard recently.

1) **Fitting.** It is found that main work (essential tacking work) accounts for only 1/6 of the total fitting manhours, while manhours for adjustment work, such as trimming or backstripping for correction of inaccuracy and




Fig. 1 RANDOH SAMPLING ANALYSIS
OF ERECTION WORK

additional fitting of pieces for hammering or jacking, account for nearly 1/2, and manhours of preparatory work, such as cleaning after work, movement to a next work spot and preparation of tools or jigs, account for nearly 1/3. It is obvious that the shipyard's target is to eliminate adjustment work, which accounts for half of the total fitting manhours.

2) Welding. As it can be seen, only 1/3 of the total welding manhours are used for substantial welding. Another 1/3 are expended by the preparatory work, such as preparation of tools, cleaning after work and movement to a next work spot, while the remaining 1/3 are consumed by various work making adjustment, such as welding of carried-over weld from assembly, remetaling to get neat edge-preparation, grinding for finishment and so on.

In addition, though it was difficult to analyze accurately, it was obvious that some portion of the substantial welding manhours in Fig. l(B) were expended for depositing excess filler metal due to wider gaps very often seen at joints. The influence of an inaccurate butt joint to the increased welding time is shown in Fig. 2. It is obvious that substantial manhours can also be saved, as well as eliminating manhours for the adjustment work, by improved accuracy.




Fig. 2 INCREMENT OF WELDING TIME DUE TO JOINT GAP AT ERECTION BUTT

#### INTRODUCTION OF A THREE-DIMENSIONAL ANALYSIS SYSTEM

As the existing measuring method was linear and planar, deflection and twisting of the three-dimensional blocks could not be The necessity for an accurately checked. instrument capable of measuring threedimensional blocks of over 10 meters square within an accuracy of several millimeters has been sought for many years. The development of a new measuring technique was taken up in 1982 by the working group for threedimensional coordinates measurement in the Super Modernization Committee of the Shipbuilders Association of Japan, with the participation of the following five companies: SOKKIA CO., LTD. as an instrument manufacturer, IHI and other three shipyards.

At the beginning, efforts were made to examine the applicability of two types of instruments, an electronic theodolite based on a triangular measurement method and an electronic distance-angle measuring instrument. It was found to be difficult to keep an accurate distance between the two instruments essential for the triangular measuring method. Moreover, due to the instability of the power source, inconvenience of transportation, and the requirement for three or more measurement technicians, it was decided not to take the dual theodolite and to concentrate to develop the application of the distance-angle measuring instrument.

During five years' effort of the working group, the distance-angle measuring method was proved to be applicable, subject to further improvement of the instrument for more accurate measurement and easier handling. After the working group dissolved, the manufacturer continued the efforts and finally reached "NET 2" as a product model in 1989 and "MONMOS" as a total measuring system in 1990, which are actually used in some shipyards in Japan.

The three-dimensional measuring instrument NET 2 was introduced in a Tokyo shipyard immediately after it came into use. Since then a hull block measuring system (hereinafter called the three-dimensional analysis system) by a personal computer incorporated with the MONMOS system has been developed so as to get the actual shape of blocks on a CRT. Other shipyards in the company have also introduced the MONMOS and another application for the ship repair field has been established. That is, to measure actual

shell form in the vicinity of damaged shell plates for the purpose of defining the shape of replacement sections.

## The MONMOS System

The following is an outline of the MONMOS system. The MONMOS system consists of a measuring instrument and a control terminal for data control. (See Fig. 3)




Fig. 3 CONFIGURATION OF THE THREE-DIMENSIONAL ANALYSIS SYSTEM

Measurement; Distance and Angle

measurement using near-


infrared rays.

Measuring

; Angle  $\pm 2$  second

accuracy Distance

±(1+2x10-<sup>6</sup>D)mm Where D is measuring distance in millimeter.




Measurable distance Target for

the ray

; 2 to 100 meters

; Microprism reflection sheet (10 to 90mm square), Rotary target (See Photos 1-A and 1-B)

and etc.



Measuring principle

; Triangulation by measuring two sides distances (I-O and I-Pi) and included angles (vertical angle and horizontal angle) (See Fig. 4)

- a. The vertical direction
   is defined to be the Z-direction.
- b. The first measuring point (0) is defined to be the origin of the coordinates axis.
- c. The X-direction is





Fig. 4 MEASURING PRINCIPLE

- defined by the second measuring point and the X-axis is defined on the X-Z plane at normal to Z-axis.
- d. Subsequent measured values are converted into coordinate values (X, Y, and Z) and recorded in the control terminal.

The main features of the system are as follows.

- a. Measurements can be carried out by one person because one instrument is capable of measuring any size.
- b. Coordinates can be combined, i.e. measurement of the back side which cannot be seen is possible by the function that stores measured values as coordinate values. Measurement can be continued with the same coordinate axis by measuring two known points (for example A and B in Fig. 5) even after moving the instrument to another point.
- c. Since the measured values are recorded as coordinate values, various kinds of numerical analyses are possible by development of analyzing software.



Outline of the Three-dimensional Analysis System

For a long time after the introduction of the hull accuracy control concept in the company, the activity of accuracy control on assembled blocks was limited to measuring length, breadth or height by a linear tapemeasure for later evaluation by manual data analysis.

When more precise blocks were called for, the traditional measuring method was not sufficient and measurement of points on any position of a block in terms of coordinate values was highlighted. But the measured points could be more than a hundred (infinitely great theoretically) and automatically the aid of calculation software became necessary to get various measured dimensions required for comparison with design data.

Thus, the company's three-dimensional analysis system was developed to comply with the above necessity with extensive applications for shipwright (this word is used to mean adjusting of a block's position properly after the block was erected and before it is fitted with adjacent blocks.) at the erection stage, the process of which is explained in Fig. 6 and summarized below.

- a. Points on a block to be measured are specified based on a standard prepared and updated through experience.
- Measured coordinates in a local axis b. are converted into coordinates in the ship's axis for comparison with design data. The conversion is generally carried out using three control points which are defined on a block and matched with the designated position in the ship's axis. When deviation from design data after conversion is found to exceed tolerances on some points due to improper matching by the above procedure, further adjustment by means of small rotation or parallel movement for closer matching can be carried out by manual operation in order to get smaller deviations.
- c. Correction work on a inaccurate block is carried out based on the deviation from the above mentioned process taking into account of a result of a simulation for forecasting joint condition with adjacent blocks. After adjacent blocks are erected, a simulation of the joint condition between those erected blocks and this assembled block, using the shipwright data of those blocks and the measured data of this block is generally carried out, whenever this block is accurate or not.
- d. The forecasted joint condition data by the above-mentioned simulation are used as a instruction for shipwright.




Fig. 6 PROCESS FLOW OF THE'S THREE-DIMENSIONAL ANALYSIS SYSTEM

# Example of Measurement and Analysis on an Assembled Block

The following is an example of using the system on **33,000** DWT Bulk Carrier blocks.

Positioning of Targets. Reflection targets were attached on more than 80 positions covering four sides and root or top of transverse webs and longitudinal on an assembled block on the ground, rotary targets were set on two points (for example, A and 13 in Fig. 7) for the combination of measured data at different locations of the instrument.




Fig. 7 POSITIONING OF TARGET

**Measured results.** Measured data were transferred into the analysis system and converted into the ship's axis. Calculated results were illustrated on the CRT as shown in Fig. 8.

**Evaluation of the results.** Figure 9 is an illustration of a displayed results for the explanation purpose.

a. The block length was longer by as much as 14mm at the top but was nearly normal at the middle and bottom. Bigger discrepancy of top length in this case was attributed to

SHIP NO : IHI FILE NAME: GSL8P. SDR

	STANDARD		LIXIT	
LENGTH BREADTH HEIGHT	± ± ±	3 2	± ± ±	5 5 3
LEVEL		7	;	15

HO		(mm)	ERROR
	MEMO	F-2	
1	L	12750.0	0.0
	В	11986.0	0.0
	Н	6335.0	0.0
	MEMO	A-2	
2	L	-2.0	+2.0
	В	14870.0	0.0
	Н	5540.0	+4.0
	MEMO	F-10	
3	L	12753.0	+3.0
	В	7449.0	-1.0
	Н	1852.3	-9.7

TOP OF TRANSVERSE WEB





Fig. 8 DISPLAY OF CALCULATED RESULTS





- smaller shrinkage than the expected value.
- b. The breadth of the block tends to decrease at the bottom, especially at the aft. The block was found to be twisted.
- c. Some dislocation of the frame top was seen in the longitudinal and vertical direction.

Actually this block was erected without correction and the detected phenomena were fed back to the next ship.


# Application to Shipwright at Erection S t a g e

Previously, the positioning of each block at the erection stage was generally carried out in order to get good relative position with adjacent blocks and the importance of positioning a block in the ship's absolute coordinate system was not widely recognized.

Now the MONMOS system can be utilized and the policy of the shipwright has been changed to position every block onto the designated position in the absolute ship's coordinates axis one by one in favor of more accurate assembled blocks.

The following explains how the system is utilized at the erection stage in the shipyard.

- a Two or three targets are attached at designated positions for shipwright on every assembled block before it is erected.
- b. The absolute ship's coordinate axis is always used as a local coordinate axis of every measurement by the MONMOS system (See Fig. 10).






Fig. 10 SHIP'S ABSOLUTED COORDINATES AXIS

- c. From time to time during the process of shipwright of a block after releasing lifting wires. measurement by the MONMOS system is carried out in cooperation with shipfitters.
- d. Final shipwright data of each block is transferred into the personal computer for the simulating calculation with subsequent blocks.

As blocks are positioned accurately one by one, by the new shipwright method. the **extent** of rework at the erection stage reduces remarkably. In addition, this method requires only one person for measurement instead of several persons as in the past. **As the** measurement for shipwright can be done at any convenient position using targets attached on a block beforehand, the access to higher clevation for measurement purpose is not required and this leads to safer working conditions (See Fig. 11).

### Further Improvement of the Threedimensional Analysis System

On the application of the system to actual production, accepting measurement errors to some extent cannot be avoided. These can be categorized as below.

a. Mechanical error : Read error in of instrument vertical

direction.

b. Errors during data : Calculation processing error at

combination or conversion of coordinate data.

c. Errors due to environment

i) Heat, moisture, : Unexpected electricity, movement of magnetism and etc.

ii) Vibration, wind, : Dislocation of etc. instruments.

iii) Backlight, : Eye-reading heat wave, shade, errors. etc.

d. Errors accompanied: Target setting
by a measuring errors, error
of measured
angle or
measured
distance due to

improper angle or distance.

Errors of category a. can be minimized




Fig. 11 IMPROVEMENT OF MEASURED METHOD

depending on future improvement of the measuring instrument, while b. can be solved by improvement of the calculation software. Though a kind of an error such as category c. i) is always inevitable to almost all measurements in production sites, analyses as to cause and effect are not yet done subject to future examination. Errors such as c. ii), and iii) are expected to be reduced by preparation of a firm and covered station for the measurement, while d. is to be improved by training and education of measurers.

In addition to countermeasures to reduce the above-mentioned errors, which are rather inherent to the instrument. improvements arc desirable on the application procedures. At the erection stage, as the combination of measured data is very often accomplished using common points for data connection, arrangement of these common points must be examined and improved by planning efforts. In assembly, it can be almost said that the accurate measuring and analyzing system of hull blocks in any size and shape has been established if numerous measurements are acceptable. However, for economical application suitable to production, there are many points to be improved further such as: determination of the minimum numbers of points on each block in order to specify the

actual block shape, feeding of design data into this measuring and analyzing system in respect to the above determined measuring points, preparation of enough geometric space for measurement, scheduling to take time for the measurement, manhours saving of target fitting and so on.

# CHALLENGE TO IMPROVE ACCURACY OF HULL BLOCKS

Measurement of assembled blocks by an improved method, the correction work on blocks before erection taking into account of shipwright data and a accurate shipwright method are introduced as described above. However, these are not the right way to improve the accuracy. In parallel with these, step by step accuracy improvement through various stages of work up to completion of hull blocks has been enhanced by recognizing the following two points as the right direction to solve the problem.

- Minimization of dimensional variation by mechanization.
- Accurate prediction of thermal deformation during burning or welding by simulation using numerical analysis software.

Efforts on the latter have been started

recently as a breakthrough to adjust parts data at the beginning of the data generating stage. These efforts will be reported on separately in the future after something has been established. Therefore, the approach to the former is explained hereunder.

# Suggestion for Mechanization through Analyses of Variation

Fig. 12(A) and (B) show how the mean values and the standard deviations at each step of fabrication change by accumulated errors, taking block length on the skin plate and length of longitudinal stiffeners as examples. In the case of block length, it can be seen that the final deviation has been doomed before plate cutting process and the mean value changes by welding


ASSEMBLED BLOCK (STANDARD SIZE) TRANSVERSE LONGITUDINAL 21 m PLATE (A) BLOCK LENGTH ACCURACY LENGTH (BB) MEAN VALUE STANDARD DEVIATION (B) JOINT ACCURACY OF LONGITUDINAL ONGITUDINA LONGI TUDINA TUDI **FRANSVER** OSITI ENGTH (BE) **MEAN VALUE** 

Fig. 12 ACCUMULATED ERROR OF BLOCK SHARE

shrinkage. In the same manner, it can be said that the deviation is doomed by cutting at prefabrication process and that the mean value changes by welding shrinkage in the case of longitudinal stiffeners.

Fig. 13(A) and (B) show actual variation data of longitudinal stiffener fillet welding to the skin plate and variation of shrinkage of skin plate per one stiffener spacing due to fillet welding. From this, it is observed that fillet welding is carried out so as to keep the designated fillet size at a minimum within variation, resulting excess deposit metal and excess heat input on the average, and that the transverse shrinkage of the panel varies accordingly.

Both of the above examples are suggesting the most effective points for future action. The source work creating the above mentioned fatal variations can be mechanized or automated with great possibilities and at the same time unavoidable welding deformation and shrinkage will be able to be predicted by the simulation for feed back to original parts definition.






Fig. 13 VARIATION OF TRANSVERSE SHRINKAGE
DUE TO FILLET WELDING

# Expected Improvement in the Hull Structural Work

The final goals of efforts by the new accuracy control concept, incorporated with reduction of variations by mechanization or automatization, heat deformation analysis for original adjustment of parts data and the development and application of the three-dimensional analysis system to assembly and erection stages, are placed on the following points:

- extensive manhour savings by eliminated rework,
- simplification of work by accurate parts or blocks for less dependency on skilled workers,
- · higher quality of the ship itself, and
- more mechanization or automatization by more improved accuracy in continuous cyclic manner.

#### **CONCLUSION**

Accuracy control efforts in IHI supported by the new concept have been explained above. As will be accepted by everybody, this new step has been very much dependent on the materialization of an accurate three-dimensional measuring system. In this respect, the endeavor by the working group in the Shipbuilders Association of Japan especially the same by SOKKIA CO., LTD. have to be much appreciated.

A super-rationalized hull erection stage is envisioned, where adjustment burning and backing-strip fitting are no longer necessary, and a wide extent of automated work is taking place. Efforts are continuing to realize this.

#### REFERENCES

#### **Books**:

- 1. Japan Shipbuilding Technology Research Association, "Study and Development Report of Updating Manufacturing Technology (I-3) Three Dimensional Coordinate Measuring Machine", 1987, The Shipbuilder Association of Japan
- 2. M. Yuuzaki et a!, "Development of Three-Dimensional Measuring and Analysis System for Shipbuilding", Ishikawajima-Harima Engineering Review, Vol. 31, No. 5, 1991
- 3. Y. Okumoto et a!, "Study on Accuracy Control of Hull Structure", Ishikawajima-Harima Engineering Review, Vol. 32, No. 2, 1992

Additional copies of this report can be obtained from the National Shipbuilding Research and Documentation Center:

# http://www.nsnet.com/docctr/

Documentation Center
The University of Michigan
Transportation Research Institute
Marine Systems Division
2901 Baxter Road
Ann Arbor, MI 48109-2150

Phone: 734-763-2465 Fax: 734-763-4862

E-mail: Doc.Center@umich.edu